





# Energy Technologies Workshop


## Ft Riley Energy Program Successes / Issues



*Duty First*



# Energy Usage Glidepath





# Ft Riley Successes / Issues



- Successes
  - Eliminate underground heat distribution
  - BPA Project
- Issues
  - Build ASHRAE 90.1-30% into PA
    - GSHP consideration for new construction
  - Eliminate excess exterior lighting from standard designs
  - Standardize design temp guidance






# Ft Riley Success #1



Energy Usage by End-Use





# Ft Riley Success #1

## Heating Plant Decentralization **Economics**

	Construction Cost (less SIOH & cont)	Maintenance Cost (annual)	Energy Cost (annual)	Discounted Payback
Pre-retrofit	*	\$116,500	\$350,608	
Decentralized	\$2,959,198**	\$133,000	\$144,947	3 years

\* Replacement of failing distribution system, boilers, and chillers = \$3.2M

\*\* Includes cost of gas piping system, modular boilers, and new chillers.






# Ft Riley Success #2

- Ft Riley signed an interagency agreement w/ BPA in FY04 to obtain 3<sup>rd</sup> party financing through BPA to execute energy projects.
- Strategy:
  - We develop energy project(s) w/ costs/savings.
  - We sign an Interagency agreement with BPA specifying payment stream.
  - BPA obtains financier and sets up financing for agency to be used to execute project(s).
  - We make annual payments to repay financing from utility bill savings.





# Ft Riley Success #2





# Ft Riley Success #2



<b><u>BPA Financed Projects</u></b>	<b><u>Cost</u></b>	<b><u>Savings</u></b>
Lighting Retrofit	\$ 167k	\$ 45k / yr
HVAC Controls Replacement	\$ 146k	\$ 18k / yr
Metering	\$ 38k	\$ 0
Ballfield Lighting Controls	\$ 29k	\$ 5k / yr
In-house costs	\$ 19k	
Finance Costs / Fees	\$ 14k	
Total Amount Financed	\$ 413k	\$ 68k / yr
Annual Payment for 10 years	\$ 52k	From \$ 68k / yr savings.








# Ft Riley Issue #1



- Enforce EPA 2005 requirement for 30% < ASHRAE 90.1
  - Recent MCA design/builders have resisted
  - Not built into PA
- Ground Source Heat Pumps
  - COE / Design/Builders will not even consider.





# Ft Riley Issue #2



Eliminate excess outside lighting on buildings




*Duty First*



# Ft Riley Issue #3



- Conflicting design temp guidance
  - UFC 3-410-01FA
    - 75-78°F for cooling
    - 68°F for heating
  - ASHRAE 55 (referenced)
    - 68°F below acceptable range
  - Interim Policy Guidance
    - 74°F  $\pm$ 2° for cooling
    - 72°F  $\pm$ 2° for heating
- Changes baseline for 90.1 Energy Cost Budget







# Ft Riley Successes / Issues





Questions?



*Duty First*



# Ft Riley Facilities




New Barracks - Good .....and Bad







# Lighting Retrofit



- Convert metal halide to T5 fluorescent; T12->T8
- T5 - Light level =  $\uparrow$  50% ; Energy Use =  $\downarrow$  42%



16



*Duty First*



# HVAC Controls Upgrade



Convert old (broken) pneumatic to DDC




*Duty First*






# HVAC Controls Upgrade



Time clock?



Thermostats?



Control Valve?



## Convert old (broken) pneumatic to DDC



*Duty First*





# Ball Field Lighting Controls



Frequently left on after morning PT



*Duty First*



# Heating Plant Decentralization

## Modular Boilers





# Heating Plant Decentralization

## **Pre-1999 Heating/Cooling**

### Central Plant

2 ea. 500 HP, gas-fired, 100-psig steam boilers

2 ea. 440-ton single-effect steam Li-Br absorption  
chillers

10,000 LF Steam Distribution System and  
Chilled Water Distribution System





# Heating Plant Decentralization

## Energy Comparison

	DHW (mbtu)	Space Htg (mbtu)	Ground loss (mbtu)	Cool (mbtu)	Total MBTU	Cost
Pre-1999	6316	22963	35040	23333	87652	\$350,608
Decentralized	4737	21528	0	2089	28353	\$144,947
				$\Delta$	<b>59299</b>	<b>\$205,661</b>

